


CIGLER MARANI UNLIMITED


architecture
within human
commitment




RAFUPC



























::: LOCAL MATERIALS – to make the courtyard more compact in materials and colours – unified transition between local-looking guesthouses and "a bit modern" library

::: PARAVENTS = SCREENWALLS = VITRINE – to display the work of women and to create "airy" architecture that will not oppress the Kafuli courtyard that is not that big as it seems when it is empty...

::: LOCAL KNOWHOW and building techniques

SIMPLE SHAPE – shape that adapts its volume to the courtyard – it uses the "forgotten space" in between library and guard's house, it uses the line of existing sunshade marquise and prolongs it to form the courtyard of UNIFIED look

::: ELEVATED FLOOR AND LIGHT STRUCTURE— there is drainage output of kafuli courtyard that cannot be plugged by solid concrete floor...

::: STEPS — TRANSITION between interior and exterior of the shelter – people are welcome to sit on it

::: PAYOTTE for the tourist again – all weaving "bazar" to be moved away from payotte to rededicate the space to relax again

RAFUPC



KAFULC

THE ART SHELTER FOR THE WOMEN - WEAVERS

CIGLER MARANI UNLIMITED

VISUALISATION

THE **ART** SHELTER FOR THE WOMEN - **WEAVERS** CIGLER MARANI UNLIMITED






VISUALISATION


CIGLER MARANI UNLIMITED






CIGLER MARANI UNLIMITED

VISUALISATION


















































Table 1 Salaries and management costs

Description	description FR	Quantity	Single price CFA	Total CFA	Total €
Construction maoeuvre (for 20 days)	Construction - maoeuvre (20 jours)	1,5 × 20	1500	45 000,0	68,4 macon pour le sol
Construction worker (for 20 days)	Construction - ouvrier (for 20 days)	2 × 20	3000	120 000,0	182,4 maneouvre
Petrol for material transport	carburant pour le transport du materiel	I	10000	10 000,0	15,2
Phone expenses	unités de telephone	I	10000	10 000,0	15,2 ouvrier pour le toit
Total				185 000,0	281,2




Table 2 Quantity and single price for material

Table 2 Quantity and single price for material	description ER	Overtity with	Single price CEA	Cinalo nuico 6	Quantity	Total price CEA	Total price 6
	description FR	Quantity unit	Single price CFA	Single price €	Quantity	Total price CFA	Total price €
floor							
concrete for foundations	beton pour les fondations	m3					
cement	ciment	baş	6 500,0			0,0	
metal beams	poutres en metal (H100)	n	6 000,0	9,1	10,0	60 000,0	
corrugated iron sheet	tole ondulée	m2	3 000,0	4,6		<u> </u>	· · · · · · · · · · · · · · · · · · ·
metal points	crochets en metal	pc	200,0	0,3			· · · · · · · · · · · · · · · · · · ·
conrete layer for floor	couche de béton non armé	m3	17 500,0	26,6	2,3	<u> </u>	· · · · · · · · · · · · · · · · · · ·
formwork for floor (300mm)	coffrage (300mm)	n	2 000,0	3,0	6,0	12 000,0	18,2
steps							
concrete for foundations for steps	beton pour les fondations des escaliers	m3	25 000,0)	0,3	6 250,0	0,0
metal structure for steps	structure métale pour les escaliers	pc	2 200,0)	5,0	11 000,0	0,0
wooden steps	escalier en bois	n	2 000,0)	7,0	14 000,0	0,0
wax layer for steps	traitement du bois - cirage avec les vernis	bouteille	2 800,0)	1,0	2 800,0	0,0
vertical structure							
concrete foundation for columns	beton pour les fondations des colonnes	m3	25 000,0)	0,3	6 250,0	0,0
cement	ciment	baş	6 500,0	9,9		0,0	0,0
metal columns (dia 7,5, height 2500mm)	colonnes en métal (dia 7,5, hauteur 2500mm)	Р	8 000,0)	2,0	16 000,0	0,0
metal columns (dia 7,5, height 3200mm)	colonnes en métal (dia 7,5, hauteur 3200mm)	Р	10 000,0	15,2	2,0	20 000,0	30,4
paravan partitions				0,0			
frames - workforce	cadres en bois - travail	р	2 500,0	3,8	19,0	47 500,0	72,2
wood fro frames	bois pour les cadres	n	2 000,0	3,0	6,0	12 000,0	18,2
weaved fabrics (width 40cm)	tissus (largeur 40cm)	n	900,0) ,4	42,0	37 800,0	57,5
roof				0,0			
beams 100*70mm	poutre en bois 100*70mm	n	ı 1 400,0	2,1	56,8	79 520,0	120,9
contrabeams 80*60mm	contrapoutres 80*60mm	n	1 200,0) 1,8	75,2	90 240,0	137,2
straw	paille	m2	2 000,0	3,0	36,0	72 000,0	109,4
others				0,0			
demolition and cleaning	demolition et nettoyage	P	5 000,0	7,6	1,0	5 000,0	7,6
change of the orientation of Guardian's door	renversement de la porte du guardian	P		7,6	1,0	5 000,0	

Table 3 Summary

Description EN	description FR	CFA	€
salaries et management	salaires	185 000,0	281,2
Material	materiel	609 235,0	840,5
Reserve (5%)	reserve	39 711,8	60,4
Total costs		833 946,8	1 182,0

MATURI





CIGLER MARANI UNLIMITED

CIGLER MARANI ARCHITECTS

CIGLER MARANI UNLIMITED

architecture

""ithin human

within human commitment

http://unlimitedcma.com